



कुम्मायक गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय



प.सं. :- ०७८/७९

च.नं. :-

१ नं. प्रदेश, नेपाल

मिति: २०७८।०५।१५

पुरानो भवन मर्मत गर्ने कार्यको लागि दररेट पेश गर्ने बारे सूचना

प्रस्तुत विषयमा कुम्मायक गाउँपालिकाको आँखा उपचार केन्द्रको भवन मर्मत गर्नुपर्ने भएकोले यसै सूचना साथ संलग्न BOQ मा उल्लेखित कार्य गर्नको लागि यस गाउँपालिकामा सूचीकृत इच्छुक इजाजत प्राप्त निर्माण व्यवसायिहरुबाट यो सूचना प्रकाशन भएको मितिले ७ (सात) दिन भित्र दररेट पेश गर्नुहुन यो सूचना प्रकाशन गरिएको छ। रीत नपुगी आएको निवेदनलाई मान्यता दिइने छैन।

गणेश अधिकारी

प्रमुख प्रशासकीय अधिकृत



कुम्मायक गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
यासोक, पाँचथर



BILL OF QUANTITY (BOQ)

योजनाको नाम:
कोटेसन नं.:

कुम्मायक आँखा उपचार केन्द्र भवन मर्मत
KRM/Q/WORKS/2078/079-01

SL.	Item Descriptions	Unit	Quantity	Rate in Figure(NRS)	Rate in Words	Total Amount (NRS)
A.	Provisional Sum					
1	Provide and Install the Project Sign Board of adequate Size as suggested by an Engineer	Nos.	1	1000.00		1000.00
	Total of Provisional Sum					1000.00
B.	Civil Works					
1	Dismantaling and removing away from site, Fractured Stone Masonry Wall in c/s mortar.	Cum.	0.738			
2	Earthwork in excavation for foundation of post,wall,etc.	Cum.	1.41			
3	Providing and laying dry stone soling work in foundation and floor all complete.	Cum.	3.82			
4	Providing and laying plain cement concrete of M15 Grade(1:2:4).	Cum.	2.10			
5	Providing and laying 12.5 mm thick cement sand plaster in 1:4 mix in wall,floor,etc.	Sqm.	46.20			
6	Providing and laying Stone masonry work in cement:sand mortar(1:6) for steps in entry porch.	Cum.	3.37			
7	Providing and laying half brick thick wall in cement sand mortar (1:4) in super structure.	Sqm.	11.97			
8	Providing,fabricating and fixing MS black pipe tubular truss.	Kgs.	371.92			
9	Providing and fixing Colored CGI Sheet (0.35mm or 45 kg/bundle)	Sqm.	33.75			
10	Providing and fixing Colored CGI Sheet Roofing ridge (0.35mm)	Rm.	3.30			
11	Providing and carving Chaukat made of local hard wood as per drawing & specification.	Cum.	0.03			
12	Supplying and fitting 38mm x 75mm soft wood frame window with 5mm glass with listi,necessary hardwares,etc. all complete.	Sqm.	2.10			
13	Proving and fitting partition wall preparing local soft wood frame of 0.61*0.915m and 10 mm commercial Plywood on both side.	Sqm.	5.02			
14	Providing,fitting and fixing flush door shutter with 38 mm thick local soft wood frame and GI plain sheet on both side including all necessary fittings.	Sqm.	1.35			
15	Providing,fabricating and fixing metal outdoor bench (2.1 m length and 0.6 m Width) with 25 mm MS square pipe frame and 20*3 mm MS Sheet.	Nos.	3.00			
16	Providing and painting two coats of enamel paint over primered surface in door and windows.	Sqm.	19.92			
17	Providing and painting two coats of aluminium paint over primered surface in metal surfaces.	Sqm.	24.34			

2/3





कुम्मायक गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
यासोक, पाँचथर



BILL OF QUANTITY (BOQ)

योजनाको नाम:
कोटेसन नं.:

कुम्मायक आँखा उपचार केन्द्र भवन मर्मत
KRM/Q/WORKS/2078/079-01

SL.	Item Descriptions	Unit	Quantity	Rate in Figure(NRS)	Rate in Words	Total Amount (NRS)
18	Providing and laying PVC carpet(Galaxy).	Rm.	8.50			
19	Providing and laying yeti carpet or eqvt.	Rm.	6.00			
20	Providing and fixing good quality curtain in door and windows.	Rm.	19.50			
21	Providing and painting Distemper powder as per specification.	Sqm.	27.00			
Total of Civil Works						
Vat @ 13 % of Civil Works						
Grand Total (A+B+Vat)						



515